BRUHAT BENGALURU MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

MODIFIED SCHEDULE - B

Name of the Work: Improvements to Roads and Drains at HMT Layout 6th, 7th Block and Surrounding area in Ward No. 14 (Vidyaranyapura).

Sl. No.	Quantity.	Description	Unit	Rates Quotation by M/s. S S Road Developers Prop: Sri. A S Mani	
				In Figures	In Words
1	705.09	Earth work Excavation by manual means for drains,canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such simillar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work.	Cum	175.96	Rupees One Hundred Seventy Five And Paise Ninety Six Only
2	98.87	Providing and laying in position Plain Cement Concrete Mix 1:3:6 (M10) for levelling course for all works in foundation. Using 40 mm nominal size graded crushed coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications.	Cum	5254.08	Rupees Five Thousand Two Hundred Fifty Four And Paise Eight Only
3	193.08	Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necesary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. M20 (The cost of steel reinforcement & formwork to be paid separately)	Cum	5928.01	Rupees Five Thousand Nine Hundred Twenty Eight And Paise One Only

Signature of the Contractor

Executive Engineer

Sl. No.	Quantity.	Description	Unit	Rates Quotation by M/s. S S Road Developers Prop: Sri. A S Mani	
				In Figures	In Words
4	11.58	Supplying, Fitting and Placing un-coated TMT bar Reinforcement in sub-structure complete as per Drawing and Technical Specifications.		87192.82	Rupees Eighty Seven Thousand One Hundred Ninety Two And Paise Eighty Two Only
5	365.85	Providing and Fixing pre cast Covering Slab made out of CC 1:2:4 with **10cm** thick and Finishing cutting, including form work,curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc, copmplete.	Sqm	1781.92	Rupees One Thousand Seven Hundred Eighty One And Paise Ninety Two Only
6	705.09	Loading and Unloading of Stone Boulder / Stone aggregates / Sand / Kankar / Moorum. (Tipper 14 m3)	Cum	70.00	Rupees Seventy Only
7	902.51	Cost of Haulage Excluding Loading and Unloading Taking output 18 t load and lead 10 km = 180 t.km	T.Km	99.33	Rupees Ninety Nine And Paise Thirty Three Only
		EIRL			
E1	41.88	Providing Size Stone masonry with hard stone in foundation & plinth with Cement mortar 1:6 (1 cement : 6 coarse sand)	Cum	5062.99	Rupees Five Thousand Sixty Two And Paise Ninety Nine Only
E2	93.42	Providing ruled pointing to cursed stone masonry with lime mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost all materials, labour, usage charges of machinery, curing complete as pre specification.	Sqm	225.15	Rupees Two Hundred Twenty Five And Paise Fifteen Only
E3	8.05	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite / trap / basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately **Mix 1:3:6 (M10) Using 20 mm nominal size graded crushed coarse aggregate**	Cum	5418.69	Rupees Five Thousand Four Hundred Eighteen And Paise Sixty Nine Only
E4	32.70	Providing and Fixing pre cast Covering Slab 230 mm thick made out of CC 1:2:4 and jelly 20mm Down size with steel reinforcement including form work,curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc, complete. As per Engineer incharge	Sqm	4331.82	Rupees Four Thousand Three Hundred Thirty One And Paise Eighty Two Only

Signture of the Contractor

Executive Engineer
Uttarayanapura Division
BBMP, Bangalore - 92